BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item no. 143

Name of the Work : Providing Rainwater Harvesting Structures, Accessories for parks coming under ward No. 5.

Sl. No.	Quantity.	Description	Unit	Rates In Figures	Rates In Words
1	29.91	Earthwork excavation for foundation of buildings,culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5 m in depth including dressing in the bottom and sides of pits and trenches ,stacking the excavated soil clear from edges of excavation with lead upto 50m.after breaking of clods complete as per specifications. Specification.	Cum	129.60	
2	13.26 1.5m to 3.0m 3.00 to 4.5m 13.26	Earthwork excavation for foundation of buildings,water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5 m in and above in width, in hard soil not exceeding 1.5 m in depth including dressing in the bottom and sides of pits and trenches ,stacking the excavated soil clear from edges of excavation with lead upto 50m.after breaking of clods complete as per specifications. Specification. (P. 5 ,I-2.4)	Cum	243.00 291.60	
3	13.26	Excavation 1.5m and above in width in soft rock without blasting for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches not exceeding 1.5m. In depth, stacking the excavated stuff from edges of excavation with lead upto 50m including cost of labours complete as per specifications. specifications. No. KBS 2.1.C/2.3.5 (P-5, I-2.6)	Cum	291.6	
4	0.33	Providing and laying in position plain cement concrete of mixed 1:4:8 using 40mm and down size graded granite metal machine mixed concrete laid layers not exceeding 15 cms thick, well compacted, in foundation and plinth cost of all materials labour , HOM of machinery , curing complete as per specifications Specification No No.KBS 4.1, 4.2. for leveleing Course in Foundation [Page 14 Item 4.3]	Cum	3939.41	
5	4.46	Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification (P. 26 I-1-6.6)	Cum	4887.17	
6	30	KSRB 2900-9.1: Providing and laying reinforced cement concrete pipe NP3 1200mm dia for culverts including pointing ends and fixing collars with cement mortar 1:2 including cost of all labour, curing complete as per specifications. Specification No. KSRB 1000, 2300 MORT & H Specification No. 1000 / 2300 (P.237/I.35.29)	Rmtr	8956.44	

ಕಾರ್ಯಪಾಲಕ ಇಂಜಿನಿಯರ್
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾ
ಬೃ.ಬೆ.ಮ.ಪಾ. ಯಲಹಂಕ ವ
ಸಹಕಾರನಗರ, ಬೆಂಗಳೂರು-92.

Sl. No.	Quantity.	Description	Unit	Rates In Figures	Rates In Words
7	9.40	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labours, curing complete as per specifications.	Sqm	143.13	
8	~~58.99~~ 58.35 (60.99)	Providing and filling in foundation with granite broken metal 100mm and down size with approved sand including and packing ramming,watering including cost of all materials and labour with all lead and lift etc., complete as per specification	Cum	1013.36	
9	5.89	Mild steel safety grill work made out of 0.5 " spacing both ways (approved rate)	Sqm	2000.00	To be Deleted
10	86.34	Providing 100mm thick RCC pre-cast slab covering (approved rate)	Sqm	1075.00	To be Deleted
11	21.20	Supplying river good sand with all lead and lift, loading and unloading and labour charges etc., complete and sa per the dirctions of the entineer in charge		958.20	
12	56.42	conveying the excavated earth, debris, silt and over burden earth to a distance of upto 15 kms. Lead by using private vehicles including and unloading charges etc., complete	cum	87.8	

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರದು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್ಲು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ ...3.(
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.

ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-92